BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT44674

MODIFIED SCHEDULE -'B'

No: EE/BTP/BBMP/E-PMT/06/2020-21, Date:03-09-2020

NAME OF WORK:- Improvements to Roads and Drains at Maruthi Saw Mill Road Surrounding Area Roads in Ward No 06 Thanisandra

Sl. No.	Approved Qty	Description	Unit	Approved Tender Rates of M/S SMLP Asphalts Prop.B B UMESHA	
				In Figures	In Words
1		Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all liftsas per specifications. iii)Dismantling Stone Masonry. B. Rubble Stone masonry in cement mortar.No. complete as per specifications and directions of the Engineer in charge.			
	42.25	Quantity upto 125%	Cum	463.00	Rupees Four Hundred Sixty Three Only
	1.63	Quantity Above 125%	Cum	463.64	Rupees Four Hundred Sixty Three and Sixty Four Paise Only
2		Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification No. 202. Complete as per specifications and directions of the Engineer in charge.			
	21.94	Quantity upto 125%	Cum	692.00	Rupees Six Hundred Ninety Two Only
3	1773.07	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods omplete as per specifications and directions of the Engineer in charge. 5km lead= 57+2.0x1.28x5 =69.80	Cum	218.00	Rupees Two Hundred Eighteen Only
4		Providing and laying Plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days Including cost of materials,labour, HOM curing form work, Scaffolding and Centering omplete as per specifications and directions of the Engineer in charge.			

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ, ಬೆಂಗಳೂರು

Scanned by CamScanner

.o.	Approved Qty	Description	Unit	Approved Tender Rates of M/S SMLP Asphalts Prop.B B UMESHA	
				In Figures	In Words
	606.57	Quantity upto 125%	Cum	5690.00	Rupees Five Thousand Six Hundred Ninety Only
5	584.69	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM Complete as per specifications and directions of the Engineer in charge.	Cum	7420.00	Rupees Seven Thousand Four Hundred Twenty Only
6		Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery omplete as per specifications and directions of the Engineer in charge.			
	39.69	Quantity upto 125%	Tonne	68266.00	Rupees Sixty Eight Thousand Two Hundred Sixty Six Only
7		Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,omplete as per specifications and directions of the Engineer in charge.(Data Rate)			
	1186.79	Quantity upto 125%	Sqm	2452.00	Rupees Two Thousand Four Hundred Fifty Two Only
8	140.52	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,omplete as per specifications and directions of the Engineer in charge.	Sqm	5686.00	Rupees Five Thousand Six Hundred Eighty Six Only
9	13.99	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing Complete as per specifications and directions of the Engineer in charge.	Cum	6031.00	Rupees Six Thousand Thirty One Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ. ಬೆಂಗಳೂರು

Scanned by CamScanner

	Approved Qty	Description	Unit	Approved Tender Rates of M/S SMLP Asphalts Prop.B B UMESHA	
				In Figures	In Words
10	1555.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,Complete as per specifications and directions of the Engineer in charge.	Nos	454.00	Rupees Four Hundred Fifty Four Only
11	279.80	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour Complete as per specifications and directions of the Engineer in charge.	Sqm	88.00	Rupees Eighty Eight Only
12	191.22	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately Complete as per specifications and directions of the Engineer in charge.	Cum	1074.00	Rupees One Thousand Seventy Four Only
13		Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and Complete as per specifications and directions of the Engineer in charge.			
	856.09	Quantity upto 125%	Cum	60.00	Rupees Sixty Only
14		Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM Complete as per specifications and directions of the Engineer in charge.			
	2347.64	Quantity upto 125%	Sqm	6.00	Rupees Six Only
15		Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density,Complete as per specifications and directions of the Engineer in charge.			
	341.28	Quantity upto 125%	Cum	2094.00	Rupees Two Thousand Ninety Four Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರ
ಬ್ಯಾಡರಾಯನಪುರ ವಿಭಾಗ
ಬೃ ಬೆ ಮ ಪಾ, ಬೆಂಗಳೂರು

Scanned by CamScanner

..	Approved Qty	Description	Unit	Approved Tender Rates of M/S SMLP Asphalts Prop.B B UMESHA	
				In Figures	In Words
16		Cement concrete pavement.Construction of un-reinforced plain cement concrete for pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008.mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire charges of machineries,all lead and lift charges etc., Complete as per specifications and directions of the Engineer in charge.			
	352.15	Quantity upto 125%	Cum	5468.00	Rupees Five Thousand Four Hundred Sixty

Signature of Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Scanned by CamScanner